

Oilwell 840-E 1500 HP
Full Drilling Rig Package with Pipes, Crew, and Camps

Location Central America
Available for charter contract, or sale
Companies Meetings U.K

DRAWWORKS: Oilwell 840-E 1500 HP with Elmagco 6032 hydromatic brake

MAST: 142 ft x 21 ft mast, 1 025 000 lb GNC (API static 750 000 lb) with 12 lines

SUBSTRUCTURE: Box-on-box 25 ft high (750 000 lb rotary and 500 000 lb set back)

POWER: 4 x Caterpillar D399 TAC with Kato 1050 kW 600 V alternators

MUD PUMPS: 2 x 1600 HP F-1600 triplex

ROTATING EQUIPMENT: 37-1/2 in rotary table.

TRAVELLING EQUIPMENT: 500 ton with 1-3/8 in EIPS drilling line

MUD SYSTEM: 1340 bbl in three tanks with 2 x Derrick Super G 4-panel linear motion shakers and 65 bbl trip tank

BOPs

21-1/4 in 2M annular with 12 in diverter valve

21-1/4 in 3M single ram

13-5/8 in 5M annular NACE trim

13-5/8 in 5M double gate NACE trim

ACCUMULATOR: Koomey 220 gal

WATER TANK: 400 bbl

HANDLING TOOLS

Kelly spinner

2 x 8000 lb air tuggers

Dedicated man riding winch

Hydraulic pipe spinner

20 in casing tong with jaws for 20 in, 13-3/8 in, 9-5/8 in and 7 in casing

TUBULARS

8000 ft 5 in 19.5 lb/ft drill pipe Grade G-105 with hardbanding to TH Hill Cat 5

3 x 9 in drill collars

12 x 8 in drill collars

18 x 6 in drill collars

10 x 5 in HWDP

AUXILIARY EQUIPMENT

Survey unit with 15 000 ft 0l.092 in wire

Fork truck 8000 lb capacity

Offices, camp, BUILDINGS

Toolpusher unit

Crew welfare unit

Tool shack

Spare container

Dog house

Crew camp